BRUHATH BANGALORE MAHANAGARA PALIKE,

SCHEDULE - B

Name of the Work: Providing Ornamental Grill and Improvement at J.P Park in Ward No.17.

Sl. No	Description	Unit	Qty	Rate(Rs.) in	
				Figure	Words
1	Fabricating, Supplying and erecting to Plumb and line, Stainless steel pipe railings as per approvid drawings using 75mm square 14 gauge pipe for verticals and neatly grinded. SS cups on either S.S pipe welded to the square Pipe. Two plates 10mm thick welded at bottom for base grip. All the joist welding including grinding, Finishing, matel patty and painting two coats of Foundation of size 0.30x0.30x0.60 and filling with C.C 1:2:4. The sets are inclusive of all materials, job work, Loding unloding etc., complete. The work should be carried as per the drawing and directions of the Enginee-in-Charge of the work. as Per Data Rate to be approved	Rmtr	158.44	8354.00	Rupees Eight Thousand Three Hundred Fifty Four Only
2	Providing and heavy duty cobbles stones 60mm thick inter lock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick and bed (average thickness) and compacting with plate vibrator having 3 tones compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its ginal compaction of paver surface joints into its final level, including cost of materials, labour and HM of machineries complete as per specification and as per the direction of the engineer in charge of the work	Sqm	45.00	833.16	Rupees Eight Hundred Thirty Three and Sixteen Paise Only

Technical Manager-3
KRIDL, BBMP Bangalore-1

Signature of contractor

Executive Engineer
R.R.Nagara Zone Division,
Bruhath Bangalore Mahanagara Palike